


CYBER COUNTY-V

Near Adibatla



LP No.: 1473/HMDA/SWDL/2026

Plan Showing The Layout In Sy No's
22/P, 26/P, 27/P, 33/P, 35/P Situated at
Sahebguda Village, Ibrahimpatnam mandal,
Rangareddy Dist.



Mortgage Plot No's :
1,2,3,& 9, 52 to 65, 70 to 86,
168 to 179, 192 to 198,
and 201 to 204

- The permission accorded does not confer any ownership rights. At a later stage if it is found that the documents are false and fabricated the permission will be revoked under Sec 450 of HMC Act 1955.
- If construction is not commenced within 6 months, building application shall be submitted afresh duly paying secured fees.
- Sanctioned Plan shall be followed strictly while making the construction.
- Sanctioned Plan copy as attested by the GHMC shall be displayed at the construction site for public view.
- Commencement Notice shall be submitted by the applicant before commencement of the building under 440 of HMC Act.
- Completion Notice shall be submitted after completion of the building & obtain occupancy certificate under 455 of HMC Act.
- Occupancy Certificate is compulsory before occupying any building.
- Public Amenities such as Water Supply, Electricity Connections will be provided only on production of occupancy certificate.
- Prior Approval should be obtained separately for any modification in the construction.
- Tree Plantation shall be done along the periphery and also in front of the premises.
- Topsoil shall be stored and shall be maintained as greenery at owners cost before issue of occupancy certificate.
- Rain Water Harvesting Structure (percolation pit) shall be constructed.
- Space for Transformer shall be provided in the site keeping the safety of the residents in view.
- Garbage House shall be made within the premises.
- Collar and silted approved for parking in the plan should be used exclusively for parking of vehicles without partition walls & rolling shutters and the same should not be converted or misused for any other purpose at any time in future as per undertaking submitted.
- No. of units as sanctioned shall not be increased without prior approval of GHMC at any time in future.
- This sanction is accorded on understanding of Road affected portion of the site to GHMC free of cost without claiming any compensation at any time as per the undertaking submitted.
- Strip of greenery on periphery of the site shall be maintained as per rules.
- Stocking of Building Materials on footpath and road margin causing obstruction to free movement of public & vehicles shall not be done, unless which permission is liable to be suspended.
- The permission accorded does not bar the application or provisions of Urban Land Ceiling & Regulations Act 1976.
- The Developer / Builder / Owner to provide service road wherever required with specified standards at their own cost.
- A safe distance of minimum 3.0mts. Vertical and Horizontal Distance between the Building & High Tension Electrical Lines and 1.5mts. for Low Tension electrical line shall be maintained.
- No front compound wall for the site abutting 18 mt. road widths shall be allowed and only low wall or Low height greenery hedge shall be allowed.
- If greenery is not maintained 10% additional property tax shall be imposed as penalty every year till the condition is fulfilled.
- All Public and Semi Public buildings above 300Sq.mts. shall be constructed to provide facilities to physically handicapped persons as per provisions of NBC of 2016.
- The mortgage built-up area shall be allowed for registration only after an Occupancy Certificate is produced.
- The Registration authority shall register only the permitted built-up area as per sanctioned plan.
- The Services like Sanitation, Plumbing, Fire Safety requirements, lifts, electrical installations etc. shall be executed under the supervision of Qualified Technical Personnel.
- Architect / Structural Engineer if changed, the consent of the previous Architect / Structural Engineer is required and to be intimated to the GHMC.
- Construction shall be covered under the contractors all risk insurance till the issue of occupancy certificate (wherever applicable).
- As per the undertaking executed in terms of G.O. Ms. No. 541 MA, dt. 17-11-2000 (wherever applicable).
- The construction shall be done by the owner only in accordance with sanctioned Plan under the strict supervision of the Architect, Structural Engineer and site engineer failing which the violators are liable for demolition besides legal action.
- The owner, builder, Architect, Structural Engineer and site engineer are jointly & severally responsible to carry out and complete the construction strictly in accordance with sanctioned plan.
- The Owner, Builder, Architect, Structural Engineer and Site Engineer are jointly and severally held responsible for the structural stability during the building construction and should strictly adhere to all the conditions in the G.O.
- The Owner / Builder should not deliver the possession of any part of built up area of the building, by way of Sale / Lease unless and until Occupancy Certificate is obtained and duly submitting the following.
- Building Completion Certificate issued by the Architect duly certifying that the building is completed as per the sanctioned plan.
- Structural Stability Certificate issued by the Structural Engineer duly certifying that the building is structurally safe and the construction is in accordance with the specified designs.
- An extract of the site registers containing inspection reports of Site Engineer, Structural Engineer and Architect.
- Insurance Policy for the completed building for a minimum period of three years.
- Structural Safety and Means of Escape Safety Requirements shall be the responsibility of the Owner, Builder/Developer, Architect and St. Engineer to provide all necessary Fire Fighting Installation as stipulated in National Building Code of India, 2016.
- Occupancy FRIE NOC Shall be Obtained from Director (EV&DM) before issue of Occupancy Certificate.
- In respect of All Non Residential Buildings and Residential Building in plot of 500 Sq.mts / 500 Sq.Yds and above, the Applicant shall comply with the provision of Telangana State Cool Roof Policy 2023-2028 and the same is mandatory for issuance of Occupancy Certificate(OC).
- A dual piping system is a type of plumbing system where two separate sets of pipes are installed to distribute water in a building. One set of pipes carries potable or drinking water, while the other set of pipes carries non-potable or reclaimed water. The potable water pipes are connected to the main water supply and distribute water for drinking, cooking, and bathing. The non-potable or reclaimed water pipes carry water that has been treated and recycled from sources like rainwater, greywater from sinks and showers, or treated wastewater.
- Parking places in buildings shall be provided with Electric Vehicle Charging Infrastructure as per Central Electricity Authority (CEA) Technical Requirements for Connection of Distributed Generation Sources, CEA Measures of Safety Regulations, 2016 and Ministry of Power Consolidated Guidelines and Standards for EV Charging Infrastructure, as amended from time to time.
- For Construction over 10,000 Sq.mt and above and in case of Group Housing Buildings where there are 100 units and above, the plumbing arrangement shall be made in a way that the potable water shall be used for drinking, cooking and bathing only and for rest of the uses, provision for dual piping system shall be made.
- New building constructions shall have to properly demarcate sections within buildings and on rooftops for housing Broadband/digital connectivity infrastructure / antennas. These areas should have access to power supply for reliable, always on services. Further, Computer Telephony Integration (CTI) of a building shall include the common duct to access the common space used as telecom room inside the building.
- Occupancy Certificate to a building shall be granted only after ensuring that the CTI as per the prescribed standards is in place and an undertaking is given by the Architect or Engineer certifying that building has ensured common access to all digital infrastructure to all service providers in accordance with plan of creation of CTI.
- The Owner / Developers shall ensure the safety of construction workers.
- The GHMC reserve the right to cancel the permission if it falls that the permission is obtained by fraud or misrepresentation or by mistake of fact.
- The Builder/Developer shall register the project in the RERA website for the plots above 500 Sq.Mtrs or more than 8 Dwelling units.

BHASHYAM REALTORS

Kavuri Hills, Madhapur, Hyderabad - 500081.



OFFICER'S NAME AND SIGNATURE
Designation: Chief Planning Officer
Approved Date: 16/01/2026